BUILDING SAFETY APPLICATION FLOW



| STAGE | WORK TO NON HIGH-RISK BUILDING Application to be Processed by Approved Inspector/Local Authority | WORK TO HIGH-RISK BUILDING Application to be processed via the Building Safety Regulator (BSR) | ESTIMATED ADDITIONAL TIMEFRAME |
|---|---|---|--------------------------------------|
| *Pre Works Application | 2+ Weeks - Application to be issued to Local Authority / Registered Building Control Approver (RBCA) | 12+ weeks (8 weeks for Existing Buildings) - Application to be submitted to Building Safety Regulator. BSR to review application. Application to be sufficiently detailed with progressed designs to meet validation criteria. Not meeting validation criteria will result in extended timescales. | 10 WEEKS |
| Declarations & Initial Notice | Declaration 1: Competence Declaration signed by client confirming Principal Contractor and Principal Designer Initial Notice issued | Declarations to be submitted as required | |
| Gateway 2 | > N/A | Notice to be issued by the Regulator prior to commencing onsite. It is an offence to commence without BSR approval | 1 WEEK |
| Prior to Commencing Works Onsite | 2 Working Days before works start on site notify Approved Inspector/Local Authority | Post Gateway 2 Approval must be issued | |
| Commencement | Notify Approved Inspector/Local Authority when works are 15% complete Site visits to be scheduled to coordinate | Higher volume of onsite visits and requests for audit and record | 18- |
| | with work programme, or when lowest slab is constructed if there is an extension or new building works. | information | 18-20 WEEKS |
| Site Inspections | Minimum Monthly inspections, recommend fortnightly to avoid non- compliance issues | Minimum Fortnightly inspections, more frequently if determined by BSR. Principal Contractor needs to ensure they document their own audit and inspections in addition to BSR inspection and submit as part of Gateway 3 | S |
| Gateway 3 Application/Pre Practical Completion Information & Inspection | To be submitted to the approved inspector prior to final inspection in a timely manner | 8 weeks prior to proposed practical completion date – application to be submitted to BSR | 8 WEEKS |
| Declaration 3 & Final Inspection | Approved Inspector/Local Authority carry out final inspection | BSR completes final inspection prior to Gateway 3 application | |
| | Declaration 3 Compliance Statement issued and signed by all of the duty holders (including the client). Evidence that Fire Safety Information has been handed to the client also required | Compliance Statement is issued and signed by all relevant duty holders, (including the client) | |
| Gateway 3 Approval | N/A | +8 weeks – application to be processed by the BSR. (Note: Regulator can request additional time if needed) | |
| Final Certificate | To be issued by Approved Inspector/ Local Authority | To be Issued by Building Safety Regulator – Property cannot be occupied without Gateway 3 approval | ~ |

* Note: As part of the planning process a Gateway one submission for new developments will be required.

* Note: A Building Regulations Principal Designer should be appointed to support the process.